

HORIZONTAL DIRECTIONAL DRILLING

Implementation of 400KV Loop Circuit Shore Approach Project (HDD)

POWER - ELECTRICITY • LARGE DIAMETER HDD



Client

Electricity & Water Authority

Main Contractor

Prysmian Powerlink

HDD Contractor

NSCC International Limited

Location

Bahrain

Start Date

November 2018

Completion Date

February 2019

Project Details

Installation of 3 shore approach crossings, 500 m each, carrying a bundle of 500 mm & 125 mm HDPE pipes, pulled from barges to onshore entry point.

Rig Type : 350 Ton Drilling Rig
Marine Equipment : Barges, multicats, tugs, speed boats and divers